MATERIALS LEGEND:

- (A) SMOOTH FINISH LIMESTONE CAP (PYRAMIDAL FORM)
- (B) ACME BRICK 2-1/4" X 3-5/8" X 7-5/8" BRICK TO BE "GOLDEN MINGLE" COLORED BRICK (CONTACT: SHAWN MCELROY 512.244.7800)
- (C) RAKED HORZ. MORTAR JOINTS, FLUSH VERT. JOINTS (MORTAR TO MATCH LIMESTONE)
- (D) 1/2" WIDE V-GROOVE EXP. JOINT IN BRICK
- (E) QUOINS - DARK ORANGE/RED BRICK (WRAP ALL FOUR SIDES - EVERY 6TH COURSE)
- (F) LIMESTONE BULLNOSE WITH 1" RADIUS
- (G) SMOOTH FACE LIMESTONE VERNEER - 2" THICK
- (H) FINISH GRADE
- (I) CONCRETE FOOTING (REF. SECTION)
- (J) EXISTING UNDISTURBED SUB GRADE
- (K) 16" X 16" NOMINAL CMU PILASTER, ALTERNATE ORIENTATION OF BLOCKS 90 FOR EACH COURSE. REINFORCE ALL 4 CELLS W/ #5 VERT. IN CELLS GROUTED SOLID W/ 3,000 PSI PEA GRAVEL AGGREGATE CONCRETE.

NOTE: CONTRACTOR TO SUBMIT BRICK SAMPLES TO LANDSCAPE ARCHITECT FOR APPROVAL



1 COLUMN "A"
ELEVATION
SCALE: 1/2" = 1'-0"

MATERIALS LEGEND:

- (A) CAST STONE ARCHITECTURAL FINIAL, REF. SPECS.
- (B) SMOOTH FINISH LIMESTONE CAP (PYRAMIDAL SHAPE)
- (C) ACME BRICK 2-1/4" X 3-5/8" X 7-5/8" BRICK TO BE "GOLDEN MINGLE" COLORED BRICK
- (D) RAKED HORZ. MORTAR JOINTS, FLUSH VERT. JOINTS (MORTAR TO MATCH LIMESTONE)
- (E) 1/2" WIDE V-GROOVE EXP. JOINT IN BRICK
- (F) QUOINS - DARK ORANGE/RED BRICK (WRAP ALL FOUR SIDES - EVERY 6TH COURSE)
- (G) LIMESTONE BULLNOSE WITH 1" RADIUS
- (H) SMOOTH FACE LIMESTONE VERNEER - 2" THICK
- (I) FINISH GRADE
- (J) CONCRETE FOOTING (REF. SECTION)
- (K) EXISTING UNDISTURBED SUB GRADE
- (L) 16" X 16" NOMINAL CMU PILASTER, ALTERNATE ORIENTATION OF BLOCKS 90 FOR EACH COURSE. REINFORCE ALL 4 CELLS W/ #5 VERT. IN CELLS GROUTED SOLID W/ 3,000 PSI PEA GRAVEL AGGREGATE CONCRETE.

NOTE: CONTRACTOR TO SUBMIT BRICK SAMPLES TO LANDSCAPE ARCHITECT FOR APPROVALS.



2 COLUMN "B"
ELEVATION
SCALE: 1/2" = 1'-0"

MATERIALS LEGEND:

- (A) SET BACK FOR LIMESTONE PANEL 2" X 12"
- (B) FINISH GRADE VARIES
- (C) 3 - TIES EQUALLY SPACED
- (D) 4 - #6 CONT. TOP AND BOTTOM W/ #3 TIES @ 12" O.C.
- (E) 4- #6 DOWELS X 6'-3"
- (F) 4 TIES @ 3" O.C. @ TOP TYP.
- (G) 18" Ø DRILLED CONCRETE SHAFT REINFORCED WITH 4 - #6 VERT. WITH #3 @18" O.C.
- (H) UNDISTURBED SUBGRADE
- (I) NATURAL LIMESTONE SUBBASE



3 MAIN ENTRANCE COLUMN FOOTING
SECTION
SCALE: 3/4" = 1'-0"

MATERIALS KEY

- (A) MASONRY TIES TYP. EVERY OTHER CMU BLOCK
- (B) ACME BRICK 2 1/4"X 3 5/8" X 7 5/8" ALL JOINTS TO BE "V" JOINTS
- (C) STAINLESS STEEL PINS (1/4"d.X 3") DRILLED INTO LIMESTONE AND SET IN MORTAR @ 16" O.C.
- (D) BULLNOSE LIMESTONE REF. DET.
- (E) CONCRETE FOOTING (REF. SECTION)
- (F) LIMESTONE PANEL
- (G) EXISTING GRADE



4 LIMESTONE BULLNOSE
PLAN VIEW
SCALE: 1/8" = 1'-0"

MATERIALS LEGEND:

- (A) 16" X 16" NOM. CMU PILASTER, TO 6' HT. ALTERNATE ORIENTATION OF BLKS. 90° EA. COURSE
- (B) BRICK COURSE REF. PLAN
- (C) #5 VERT. REINFORCED IN ALL 4 CELLS GROUTED SOLID W/ 3000 PSI PEA GRAVEL AGGREGATE COURSE
- (D) 4-#5 DOWELS TO CMU PILASTER 2'-0" INTO CONC. & 2'-4" INTO CMU
- (E) 2" OFFSET FOR LIMESTONE VERNEER
- (F) EXISTING GRADE
- (G) #5 VERT. @ 10" EA. WAY
- (H) CONCRETE FOOTING
- (I) 4-#6 CONT. TOP & BOTTOM W/ #3 TIES @ 12" O.C.
- (J) FOR PIER REF. DETAIL 3/SD-3



6 GRADE BEAM - MAIN ENTRY
SECTION
SCALE: 3/4" = 1'-0"

MATERIALS LEGEND:

- (A) 16" X 16" NOM. CMU PILASTER, TO 6' HT. GROUTED SOLID W/ 3000 PSI PEA GRAVEL ALTERNATE ORIENTATION OF BLKS. 90° EA. COURSE
- (B) BRICK COURSE REF. PLAN
- (C) #5 VERT. REINFORCED IN ALL 4 CELLS GROUTED SOLID W/ 3000 PSI PEA GRAVEL AGGREGATE COURSE
- (D) 4-#5 DOWELS TO CMU PILASTER 2'-0" INTO CONC. & 2'-4" INTO CMU
- (E) 2" OFFSET FOR LIMESTONE VERNEER
- (F) EXISTING GRADE
- (G) #5 VERT. @ 10" EA. WAY
- (H) CONCRETE FOOTING
- (I) 10-1/2"20X6" HEADED STUDS ON TUBULAR STEEL 6" X 6"
- (J) FOR PIER REF. DETAIL, 3/SD-3
- (K) TUBULAR STEEL 6" X 6" EMBED 2'-6"
- (L) FOR DOWELS REF. DET. 3/SD-3



7 MAIN ENTRY FOOTING
SECTION
SCALE: 3/4" = 1'-0"

MATERIALS LEGEND

- (A) LIMESTONE PANEL WITH "V" CUT LETTERS INFILLED WITH GOLD LITHOCHROME
- (B) BEVELED EDGE 1" WIDE
- (C) BRICK COLUMN TYP.



5 MAIN ENTRY PLAQUE DETAIL
ELEVATION
SCALE: 1" = 1'-0"

J. Robert Anderson, ASLA
Landscape Architect
1715 S. Capital of Texas Highway
Suite 105
Austin, Texas 78746

phone 512.329.8882
fax 512.329.8883
e-mail: jranders@aol.com

The University of Texas at Austin

Frank Denius Field

Owner: University of Texas
Mens Athletic Department
Address: Red River and MLK Blvd.
Austin, Texas
78701
phone: 512.471.5317
Fax: 512.471.4833

AREA MAP

DATE ISSUED: 5/06/98
REVISIONS:

DRAWN BY: TAB/TWH
REVIEWED BY: JRA

PLAN NORTH

SCALE AS INDICATED

PROJECT NUMBER:

SITE DETAILS

SD-3